

Attachment B

Deployment of a tower crew for the installation of two Sensus M400 systems in the Panama City area.

Estimate assumes the following:

- * The m400 will mount near the base of the tower/tank.
- * All electrical work will be provided by others.

Best guess assumptions have been made with how the installation will be done as well as the hardware to be used. We deploy with the ability to overcome most situations. However, should the need arise having to overnight materials, all expenses incurred thereof will be invoiced accordingly.

Estimate assumes the site will be constructed during a single deployment; second deployment charges may apply if necessary.

Antenna will mount to the top, or as near to the top, of the tower or as possible. Antenna will be on top of monopole.

Materials List Per Site:

(Estimated materials list based on commonly used items per install, count and lengths are detailed elsewhere.)

- 1 Antenna, as listed per site
- 1 Antenna mounting kit (non-penetrating roof mount and mag-mount are not included)
- 180' Coax
- 2 Coax Connectors
- Coax routing hardware and hangers
- 1 PolyPhaser
- 3 Universal Ground Kit for coax, 5' lead w/ 3/8' lug
- 2 Universal weatherproofing kit (WK-U)
- 1 Grounding materials
- 1 Ground bar
- Ground rod(s)
- 2 Jumpers

Wastewater treatment plant

(50' monopole w/pegs - new)

- * DB589-Y
- * Counterpoise ground package for the pole.

Panama Water Tank

641 US-231, Panama City, FL 32405

(NW corner of SR77 & US HWY231)

- * DB589-Y
- * Mag-mount